

# FGM-PARALLEL LLC

## FLORIDA BUILDING CODE TEST REPORT

### SCOPE OF WORK

TAS 201, TAS 202, AND TAS 203 TESTING ON 6" AND 12" PROFILE CLADDING

### REPORT NUMBER

R9929.01-109-18 R1

### TEST DATES

02/11/25 – 03/21/25

### ISSUE DATE

05/01/25

### REVISION DATE

05/13/25

### RECORD RETENTION END DATE

03/21/35


### PAGES

39

### DOCUMENT CONTROL NUMBER

RT-R-AMER-Test-2816 (06/21/24)

© 2017 INTERTEK





Total Quality. Assured.

130 Derry Court  
York, Pennsylvania 17406

Telephone: 717-764-7700  
Facsimile: 717-764-4129  
www.intertek.com/building

**TEST REPORT FOR FGM-PARALLEL LLC**

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

**REPORT ISSUED TO**

**FGM-PARALLEL LLC**

2750 S. Raritan Street

Englewood, Colorado 80110

**SECTION 1**

**SCOPE**

Architectural Testing, Inc. (an Intertek company) dba Intertek Building & Construction (B&C) was contracted by FGM-Parallel LLC to perform TAS 201, TAS 202, and TAS 203 testing in accordance with Florida Building Code for High Velocity Hurricane Zone requirements on their C-B6 and C-B12, 6" and 12" Profile Cladding. Results obtained are tested values and were secured by using the designated test methods. Testing was conducted at the Intertek B&C test facility in York, Pennsylvania. This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

For INTERTEK B&C:

<b>COMPLETED BY:</b>	Jason R. Zeller
<b>TITLE:</b>	Technician – Product Testing
<b>SIGNATURE:</b>	
<b>DATE:</b>	05/13/25

<b>REVIEWED BY:</b>	Tanya A. Dolby, P.E.
<b>TITLE:</b>	Engineering Manager – Engineering Services
<b>SIGNATURE:</b>	
<b>DATE:</b>	05/13/25

JRZ:mas

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

### SECTION 2

#### SUMMARY OF TEST RESULTS

The specimens tested met the performance requirements set forth in the protocols.

**Product Type:** Cladding

**Series/Model:** C-B6, 6" Profile on plywood sheathing

SPEC.	TEST PROTOCOL	DESIGN PRESSURE
1A and 2A	TAS 202	+120.00 / -120.00 psf
3A, 4A, and 5A	TAS 203	-120.00 psf

**Product Type:** Cladding

**Series/Model:** C-B12, 12" Profile on plywood sheathing

SPEC.	TEST PROTOCOL	DESIGN PRESSURE
1B and 2B	TAS 202	+120.00 / -120.00 psf
3B and 4B	TAS 203	-120.00 psf

**Product Type:** Cladding

**Series/Model:** C-B12, 12" Profile on gypsum sheathing

SPEC.	TEST PROTOCOL	DESIGN PRESSURE
1C and 2C	TAS 202	+120.00 / -120.00 psf
3C	TAS 201/203 (Large Missile)	+120.00 / -120.00 psf

### SECTION 3

#### TEST METHODS

The specimens were evaluated in accordance with the following:

**TAS 201-94**, *Impact Test Procedures*

**TAS 202-94**, *Criteria for Testing Impact & Non Impact Resistant Building Envelope Components Using Uniform Static Air Pressure*

**TAS 203-94**, *Criteria for Testing Products Subject to Cyclic Wind Pressure Loading*

## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

### SECTION 4

#### MATERIAL SOURCE/INSTALLATION

Test specimens were provided by the client. Representative samples of the test specimens will be retained by Intertek B&C for a minimum of ten years from the test completion date.

The specimens were installed into a Spruce-Pine-Fir wood test buck. The rough opening allowed for a no shim space. The interior perimeter of the specimens was sealed with sealant. Installation of the tested product was performed by the client.

##### **Specimens 1A and 1B Test Wall Construction:**

The test walls were constructed of nominal 2x6 studs, spaced 16" on center. The studs were secured to the head and sill using #10 x 3" flat head screws, through the head and sill, into studs. The test walls were sheathed with two 4' x 8', 5/8" thick sheets of 5-ply plywood with a single horizontal joint and secured to the studs with #8 x 1-5/8" flat head screws. The test wall was covered with Tyvek® CommercialWrap® and flashed with Tyvek® tape. The test walls were wrapped with nominal 2x10 lumber and secured with #10 x 3" flat head screws, spaced 10" on center and staggered along the perimeter, through the wrap and into studs. The exterior perimeter of the test wall was sealed with sealant.

##### **Specimens 2A through 5A and 2B through 4B Test Wall Construction:**

The test walls were constructed of nominal 2x6 studs, spaced 16" on center. The studs were secured to the head and sill using #10 x 3" flat head screws, through the head and sill, into studs. The test walls were sheathed with two 4' x 8', 5/8" thick sheets of 5-ply plywood with a single horizontal joint and secured to the studs with #8 x 1-5/8" flat head screws. The test walls were wrapped with nominal 2x10 lumber and secured with #10 x 3" flat head screws, spaced 10" on center and staggered along the perimeter, through the wrap and into studs.

##### **Specimens 1C Test Wall Construction:**

The test walls were constructed of nominal 2x6 studs, spaced 16" on center. The studs were secured to the head and sill using #10 x 3" flat head screws, through the head and sill, into studs. The test walls were sheathed with two 4' x 8', 5/8" thick sheets exterior gypsum sheathing with a single horizontal joint and secured to the studs with #8 x 1-5/8" flat head screws. The test wall was covered with Tyvek® CommercialWrap® and flashed with Tyvek® tape. The test walls were wrapped with nominal 2x10 lumber and secured with #10 x 3" flat head screws, spaced 10" on center and staggered along the perimeter, through the wrap and into studs. The exterior perimeter of the test wall was sealed with sealant.

**TEST REPORT FOR FGM-PARALLEL LLC**

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

**Specimens 2C Test Wall Construction:**

The test walls were constructed of nominal 2x6 studs, spaced 16" on center. The studs were secured to the head and sill using #10 x 3" flat head screws, through the head and sill, into studs. The test walls were sheathed with two 4' x 8', 5/8" thick sheets exterior gypsum sheathing with a single horizontal joint and secured to the studs with #8 x 1-5/8" flat head screws. The test walls were wrapped with nominal 2x10 lumber and secured with #10 x 3" flat head screws, spaced 10" on center and staggered along the perimeter, through the wrap and into studs.

**Specimens 3C Test Wall Construction:**

The test walls were constructed of nominal 2x6 studs, spaced 16" on center with double end studs. The studs were secured to the head and sill using #10 x 3" flat head screws, through the head and sill, into studs. The test walls were sheathed with two 4' x 8', 5/8" thick sheets exterior gypsum sheathing with a single horizontal joint and secured to the studs with #8 x 1-5/8" flat head screws. The test walls were wrapped with nominal 2x10 lumber and secured with #10 x 3" flat head screws, spaced 10" on center and staggered along the perimeter, through the wrap and into studs.

**Specimens 1A through 5A Installation:**

A 92" long extruded aluminum cladding starter piece (C-STR) was fastened horizontally at the top of the test wall using 1/4-10 x 1-1/2" hex head screws, spaced 24" on center, through the starter piece and sheathing, into head stud. Two 96" long extruded aluminum cladding termination trim bases (C-TTM) were fastened vertically at the end studs using 1/4-10 x 1-1/2" hex head screws, spaced 24" on center, through the termination base into sheathing. One 92" long extruded aluminum cladding termination base (C-TTM) was fastened horizontally to the bottom of the test wall with using 1/4-10 x 1-1/2" hex head screws, spaced 24" on center, through the starter piece and sheathing, into sill stud. The first 6" cladding board (C-B6) was interlocked into the starter piece and secured using extruded aluminum cladding expansion clips (C-EC) at the bottom of the cladding board, at ends and spaced 32" on center, fastened using one 1/4-10 x 1-1/2" hex head screw per clip, through clip and sheathing, into studs. The end clip fasteners were fastened through the clips and into sheathing. 14 more 6" cladding board (C-B6) courses were installed onto the test wall in the same manner as the first course. The final course was trimmed horizontally flush with the bottom cladding termination base. Cladding termination trim tops (C-TTF) were snapped into place over the length of each cladding termination base (C-TTM) securing the ends of each course and the bottom of the lower course with a 1/2" overlap.

**TEST REPORT FOR FGM-PARALLEL LLC**

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

**Specimens 1B through 4B Installation:**

A 92" long extruded aluminum cladding starter piece (C-STR) was fastened horizontally at the top of the test wall using 1/4-10 x 1-1/2" hex head screws, spaced 24" on center, through the starter piece and sheathing, into head stud. Two 96" long extruded aluminum cladding termination trim bases (C-TTM) were fastened vertically at the end studs using 1/4-10 x 1-1/2" hex head screws, spaced 24" on center, through the termination base into sheathing. One 92" long extruded aluminum cladding termination base (C-TTM) was fastened horizontally to the bottom of the test wall with using 1/4-10 x 1-1/2" hex head screws, spaced 24" on center, through the starter piece and sheathing, into sill stud. The first 12" cladding board (C-B12) was interlocked into the starter piece and secured using extruded aluminum cladding expansion clips (C-EC) at the bottom of the cladding board, at ends and spaced 16" on center, fastened using one 1/4-10 x 1-1/2" hex head screw per clip, through clip and sheathing, into field studs. The end clip fasteners were fastened through the clips and into sheathing. Seven more 12" cladding board (C-B12) courses were installed onto the test wall in the same manner as the first course. The final course was trimmed horizontally flush with the bottom cladding termination base. Cladding termination trim tops (C-TTF) were snapped into place over the length of each cladding termination base (C-TTM) securing the ends of each course and the bottom of the lower course with a 1/2" overlap.

**Specimens 1C and 2C Installation:**

A 92" long extruded aluminum cladding starter piece (C-STR) was fastened horizontally at the top of the test wall using 1/4-10 x 1-1/2" hex head screws, spaced 24" on center, through the starter piece and gypsum sheathing, into head stud. Two 96" long extruded aluminum cladding termination trim bases (C-TTM) were fastened vertically at the end studs using 1/4-10 x 1-1/2" hex head screws, spaced 24" on center, through the termination base into gypsum sheathing. One 92" long extruded aluminum cladding termination base (C-TTM) was fastened horizontally to the bottom of the test wall with using 1/4-10 x 1-1/2" hex head screws, spaced 24" on center, through the starter piece and gypsum sheathing, into sill stud. The first 12" cladding board (C-B12) was interlocked into the starter piece and secured using extruded aluminum cladding expansion clips (C-EC) at the bottom of the cladding board, at ends and spaced 16" on center, fastened using one 1/4-10 x 2-1/2" hex head screw per clip, through clip and gypsum sheathing, into field studs. The end clip fasteners were fastened through the clips and into sheathing. Seven more 12" cladding board (C-B12) courses were installed onto the test wall in the same manner as the first course. The final course was trimmed horizontally flush with the bottom cladding termination base. Cladding termination trim tops (C-TTF) were snapped into place over the length of each cladding termination base (C-TTM) securing the ends of each course and the bottom of the lower course with a 1/2" overlap.

## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

### Specimens 3C Installation:

A 92" long extruded aluminum cladding starter piece (C-STR) was fastened horizontally at the top of the test wall using 1/4-10 x 1-1/2" hex head screws, spaced 24" on center, through the starter piece and gypsum sheathing, into head stud. Two 96" long extruded aluminum cladding termination trim bases (C-TTM) were fastened vertically at the end studs using 1/4-10 x 1-1/2" hex head screws, spaced 24" on center, through the termination base into gypsum sheathing. One 92" long extruded aluminum cladding termination base (C-TTM) was fastened horizontally to the bottom of the test wall with using 1/4-10 x 1-1/2" hex head screws, spaced 24" on center, through the starter piece and gypsum sheathing, into sill stud. The first 12" cladding board (C-B12) was interlocked into the starter piece and secured using extruded aluminum cladding expansion clips (C-EC) at the bottom of the cladding board, at ends and spaced 16" on center, fastened using one 1/4-10 x 2-1/2" hex head screw per clip, through clip and gypsum sheathing, into field studs. The end clip fasteners were fastened through the clips and gypsum sheathing, into the double end studs. Seven more 12" cladding board (C-B12) courses were installed onto the test wall in the same manner as the first course. The final course was trimmed horizontally flush with the bottom cladding termination base. Cladding termination trim tops (C-TTF) were snapped into place over the length of each cladding termination base (C-TTM) securing the ends of each course and the bottom of the lower course with a 1/2" overlap.

## SECTION 5

### EQUIPMENT

**Cannon:** Constructed from steel piping utilizing compressed air to propel the missile, A1207

**Missile:** 2x4 Southern Pine

**Timing Device:** Electronic beam type, A1207

**Cycling Mechanism:** Computer controlled centrifugal blower with electronic pressure measuring device, 005644

**Deflection Measuring Device:** Linear transducers, 64325, 64460, INT03248, INT03249, INT03252

**Spray Rack:** 003956E, 003956F

## SECTION 6

### LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
David Carmack	Parallel Architecture
Jerod Shaeffer	Parallel Architecture
Ken R. Stough	Intertek B&C
Tanya A. Dolby, P.E.	Intertek B&C
Jason R. Zeller	Intertek B&C

## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

### SECTION 7

#### TEST SPECIMEN DESCRIPTION

**Product Type:** Cladding

**Series/Model:** C-B6, 6" Profile

**Product Sizes:**

OVERALL AREA:	WIDTH	HEIGHT
64.0 ft <sup>2</sup>	inches	inches
Overall size	96	96
Cladding board size	93	7-1/2

**Product Type:** Cladding

**Series/Model:** C-B12, 12" Profile

**Product Sizes:**

OVERALL AREA:	WIDTH	HEIGHT
64.0 ft <sup>2</sup>	inches	inches
Overall size	96	96
Cladding board size	93	13-3/8

### SECTION 8

#### TEST RESULTS

**Protocol TAS 202-94, Static Air Pressure**

**Test Dates:** 02/11/25

The temperature during testing was 64°F. The results are tabulated as follows:

**Test Specimen #1A: Air Leakage per TAS 202**

TITLE OF TEST	RESULTS	ALLOWED	NOTE
<b>Air Leakage,</b> Infiltration per TAS 202 at 1.57 psf (25 mph)	<0.01 cfm/ft <sup>2</sup>	Report only	1
<b>Air Leakage,</b> Infiltration per TAS 202 at 6.27 psf (50 mph)	<0.01 cfm/ft <sup>2</sup>	Report only	1

**Note 1:** Test Date 02/11/25 / Time: 10:00 AM



**TEST REPORT FOR FGM-PARALLEL LLC**

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

**Test Specimen #1A: Preload and Design Load per TAS 202**

INDICATOR LOCATION	Deflection at +90.00 psf	DEFLECTION (in.)		Permanent Set at +90.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	0.34	0.06	N/A	0.01	0.02	N/A
2	0.40			0.03		
3	0.35			0.02		
4	0.35	0.01		0.02	0.01	
5	0.34			0.01		
6	0.35			0.02		
INDICATOR LOCATION	Deflection at +120.00 psf	DEFLECTION (in.)		Permanent Set at +120.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	0.47	0.07	0.53	0.02	0.01	N/A
2	0.54			0.03		
3	0.47			0.02		
4	0.47	0.01	0.10	0.02	<0.01	
5	0.47			0.02		
6	0.48			0.02		

**Test Specimen #2A: Preload and Design Load per TAS 202**

INDICATOR LOCATION	Deflection at -90.00 psf	DEFLECTION (in.)		Permanent Set at -90.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	0.92	0.15	N/A	0.09	0.01	N/A
2	1.06			0.10		
3	0.90			0.09		
4	0.91	0.04		0.09	<0.01	
5	0.92			0.09		
6	0.85			0.08		
INDICATOR LOCATION	Deflection at -120.00 psf	DEFLECTION (in.)		Permanent Set at -120.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	1.43	0.22	0.53	0.19	0.03	N/A
2	1.65			0.23		
3	1.44			0.22		
4	1.43	0.05	0.10	0.20	<0.01	
5	1.43			0.19		
6	1.34			0.18		

## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

### Test Specimen #1A: Water Penetration per TAS 202

TITLE OF TEST	RESULTS	ALLOWED	NOTE
Water Penetration, per TAS 202 15% of Positive Design Pressure at 18.00 psf	Pass	No leakage	2

**Note 2:** Without insect screen.

### Test Specimen #1A: Structural Overload Load per TAS 202

INDICATOR LOCATION	Deflection at +180.00 psf	DEFLECTION (in.)		Permanent Set at +180.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	0.71	0.12	N/A	0.03	0.01	0.13
2	0.82			0.04		
3	0.70			0.03		
4	0.72	0.01		0.03	<0.01	0.02
5	0.70			0.03		
6	0.70			0.03		

### Test Specimen #2A: Structural Overload Load per TAS 202

INDICATOR LOCATION	Deflection at +180.00 psf	DEFLECTION (in.)		Permanent Set at +180.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	1.85	0.26	N/A	0.29	0.04	0.13
2	2.12			0.34		
3	1.87			0.32		
4	1.85	0.05		0.30	0.01	0.02
5	1.85			0.29		
6	1.75			0.27		

**Note 3:** Positive and negative uniform static load test loads were held for 30 seconds.

**Note 4:** Tape and film were used to seal against air leakage during structural testing. In our opinion, the tape and film did not influence the results of the test.

**Note 5:** See Sketch #1 for indicator locations. Deflection/permanent set reported is the overall deflection between three points (longest unsupported span) which accounts for support movement.

**TEST REPORT FOR FGM-PARALLEL LLC**

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

**Protocol TAS 203-94, Cyclic Wind Pressure Loading**

**Test Date(s):** 02/19/25

The temperature during testing was 60° - 65°F. The results are tabulated as follows:

**Test Specimen #3A: Cyclic Test Spectrum and Average Cycle Time per TAS 203**

DESIGN PRESSURE	STAGE		
-120.00 psf	1	2	3
<b>NEGATIVE PRESSURE RANGE (psf)</b>	0 – 60.00	0 – 72.00	0 – 156.00
<b>AVERAGE CYCLE TIME (sec.)</b>	2.87	2.91	N/A
<b>NUMBER OF CYCLES</b>	600	70	1

**Test Specimen #3A: Negative Cyclic Load per TAS 203**

INDICATOR LOCATION	NET MAXIMUM DEFLECTION (in.)	NET PERMANENT SET (in.)	PERCENT RECOVERY	
			MEASURED %	ALLOWED %
1-3	0.205	0.005	98	> 90
4-6	0.040	0.005	88	> 90

**General Note:** Test Application Standard (TAS) 203, Criteria for Testing Products Subject to Cyclic Wind Pressure Loading states, "Assemblies shall be tested with no resultant failure or distress and shall have a recovery of at least 90% over maximum deflection." In cases where assemblies experience very small deflections while testing, accurately measuring permanent set is beyond the capabilities of the measuring equipment. Permanent set will be stated with the highest accuracy possible allowed by the measuring equipment but may not meet the 90 percent recovery. For those cases, consideration should be given to the fact that the deflections and permanent set are so small as to be irrelevant and should not be considered a failure.

**Test Specimen #4A: Cyclic Test Spectrum and Average Cycle Time per TAS 203**

DESIGN PRESSURE	STAGE		
-120.00 psf	1	2	3
<b>NEGATIVE PRESSURE RANGE (psf)</b>	0 – 60.00	0 – 72.00	0 – 156.00
<b>AVERAGE CYCLE TIME (sec.)</b>	2.89	2.97	N/A
<b>NUMBER OF CYCLES</b>	600	70	1

**Test Specimen #4A: Negative Cyclic Load per TAS 203**

INDICATOR LOCATION	NET MAXIMUM DEFLECTION (in.)	NET PERMANENT SET (in.)	PERCENT RECOVERY	
			MEASURED %	ALLOWED %
1-3	0.225	0.020	91	> 90
4-6	0.230	0.010	97	> 90

**TEST REPORT FOR FGM-PARALLEL LLC**

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

**Test Specimen #5A: Cyclic Test Spectrum and Average Cycle Time per TAS 203**

DESIGN PRESSURE	STAGE		
	1	2	3
-120.00 psf			
<b>NEGATIVE PRESSURE RANGE (psf)</b>	0 – 60.00	0 – 72.00	0 – 156.00
<b>AVERAGE CYCLE TIME (sec.)</b>	2.87	2.96	N/A
<b>NUMBER OF CYCLES</b>	600	70	1

**Test Specimen #5A: Negative Cyclic Load per TAS 203**

INDICATOR LOCATION	NET MAXIMUM DEFLECTION (in.)	NET PERMANENT SET (in.)	PERCENT RECOVERY	
			MEASURED %	ALLOWED %
1-3	0.270	0.015	94	> 90
4-6	0.235	0.005	98	> 90

**Note 6:** See Sketch #1 for indicator locations. Deflection/permanent set reported is the overall deflection between three points (longest unsupported span) which accounts for support movement.

**Protocol TAS 202-94, Static Air Pressure**

Test Dates: 02/13/25

The temperature during testing was 65°F. The results are tabulated as follows:

**Test Specimen #1B: Air Leakage per TAS 202**

TITLE OF TEST	RESULTS	ALLOWED	NOTE
<b>Air Leakage,</b> Infiltration per TAS 202 at 1.57 psf (25 mph)	<0.01 cfm/ft <sup>2</sup>	Report only	1
<b>Air Leakage,</b> Infiltration per TAS 202 at 6.27 psf (50 mph)	<0.01 cfm/ft <sup>2</sup>	Report only	1

**Note 7:** Test Date 02/11/25 / Time: 11:30 AM

**TEST REPORT FOR FGM-PARALLEL LLC**

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

**Test Specimen #1B: Preload and Design Load per TAS 202**

INDICATOR LOCATION	Deflection at +90.00 psf	DEFLECTION (in.)		Permanent Set at +90.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	0.34	0.02	N/A	0.02	<0.01	N/A
2	0.36			0.02		
3	0.35			0.02		
4	0.35	0.02		0.02	<0.01	
5	0.34			0.02		
6	0.37			0.02		
INDICATOR LOCATION	Deflection at +120.00 psf	DEFLECTION (in.)		Permanent Set at +120.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	0.46	0.02	0.27	0.04	0.01	N/A
2	0.49			0.03		
3	0.49			0.03		
4	0.47	0.03	0.20	0.03	0.01	
5	0.46			0.04		
6	0.50			0.03		

**Test Specimen #2B: Preload and Design Load per TAS 202**

INDICATOR LOCATION	Deflection at -90.00 psf	DEFLECTION (in.)		Permanent Set at -90.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	0.65	0.01	N/A	0.04	0.01	N/A
2	0.65			0.03		
3	0.63			0.04		
4	0.55	0.12		0.04	<0.01	
5	0.65			0.04		
6	0.51			0.04		
INDICATOR LOCATION	Deflection at -120.00 psf	DEFLECTION (in.)		Permanent Set at -120.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	0.89	0.02	0.27	0.05	0.01	N/A
2	0.89			0.04		
3	0.85			0.04		
4	0.77	0.15	0.20	0.05	<0.01	
5	0.89			0.05		
6	0.71			0.05		

## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

### Test Specimen #1B: Water Penetration per TAS 202

TITLE OF TEST	RESULTS	ALLOWED	NOTE
Water Penetration, per TAS 202 15% of Positive Design Pressure at 18.00 psf	Pass	No leakage	2

**Note 8:** Without insect screen.

### Test Specimen #1B: Structural Overload Load per TAS 202

INDICATOR LOCATION	Deflection at +180.00 psf	DEFLECTION (in.)		Permanent Set at +180.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	0.68	0.03	N/A	0.05	0.01	0.06
2	0.73			0.04		
3	0.73			0.05		
4	0.70	0.03		0.04	0.01	0.05
5	0.68			0.05		
6	0.62			0.04		

### Test Specimen #2B: Structural Overload Load per TAS 202

INDICATOR LOCATION	Deflection at -180.00 psf	DEFLECTION (in.)		Permanent Set at +180.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	1.47	0.06	N/A	0.08	0.01	0.06
2	1.48			0.07		
3	1.38			0.08		
4	1.30	0.22		0.09	0.01	0.05
5	1.47			0.08		
6	1.20			0.09		

**Note 9:** Positive and negative uniform static load test loads were held for 30 seconds.

**Note 10:** Tape and film were used to seal against air leakage during structural testing. In our opinion, the tape and film did not influence the results of the test.

**Note 11:** See Sketch #2 for indicator locations. Deflection/permanent set reported is the overall deflection between three points (longest unsupported span) which accounts for support movement.

## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

### Protocol TAS 203-94, Cyclic Wind Pressure Loading

Test Date(s): 02/17/25 – 02/18/25

The temperature during testing was 64°F. The results are tabulated as follows:

#### Test Specimen #3B: Cyclic Test Spectrum and Average Cycle Time per TAS 203

DESIGN PRESSURE	STAGE		
	1	2	3
-120.00 psf			
NEGATIVE PRESSURE RANGE (psf)	0 – 60.00	0 – 72.00	0 – 156.00
AVERAGE CYCLE TIME (sec.)	2.89	3.04	N/A
NUMBER OF CYCLES	600	70	1

#### Test Specimen #3B: Negative Cyclic Load per TAS 203

INDICATOR LOCATION	NET MAXIMUM DEFLECTION (in.)	NET PERMANENT SET (in.)	PERCENT RECOVERY	
			MEASURED %	ALLOWED %
1-3	0.050	0.005	90	> 90
4-6	0.245	0.010	96	> 90

**Note 12:** See Sketch #2 for indicator locations. Deflection/permanent set reported is the overall deflection between three points (longest unsupported span) which accounts for support movement.

#### Test Specimen #4B: Cyclic Test Spectrum and Average Cycle Time per TAS 203

DESIGN PRESSURE	STAGE		
	1	2	3
-120.00 psf			
NEGATIVE PRESSURE RANGE (psf)	0 – 60.00	0 – 72.00	0 – 156.00
AVERAGE CYCLE TIME (sec.)	2.91	3.06	N/A
NUMBER OF CYCLES	600	70	1

#### Test Specimen #4B: Negative Cyclic Load per TAS 203

INDICATOR LOCATION	NET MAXIMUM DEFLECTION (in.)	NET PERMANENT SET (in.)	PERCENT RECOVERY	
			MEASURED %	ALLOWED %
1-3	0.090	<0.010	>99	> 90
4-6	0.165	0.010	94	> 90

**Note 13:** See Sketch #2 for indicator locations. Deflection/permanent set reported is the overall deflection between three points (longest unsupported span) which accounts for support movement.

**TEST REPORT FOR FGM-PARALLEL LLC**

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

**Protocol TAS 202-94, Static Air Pressure**

**Test Dates:** 02/12/25

The temperature during testing was 61°-64°F. The results are tabulated as follows:

**Test Specimen #1C: Air Leakage per TAS 202**

TITLE OF TEST	RESULTS	ALLOWED	NOTE
<b>Air Leakage,</b> Infiltration per TAS 202 at 1.57 psf (25 mph)	<0.01 cfm/ft <sup>2</sup>	Report only	1
<b>Air Leakage,</b> Infiltration per TAS 202 at 6.27 psf (50 mph)	<0.01 cfm/ft <sup>2</sup>	Report only	1

**Note 14:** Test Date 02/12/25 / Time: 9:00 AM

**Test Specimen #1C: Preload and Design Load per TAS 202**

INDICATOR LOCATION	Deflection at +90.00 psf	DEFLECTION (in.)		Permanent Set at +90.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	0.34	0.04	N/A	0.03	0.01	N/A
2	0.34			0.03		
3	0.27			0.02		
4	0.34	0.01		0.03	<0.01	
5	0.34			0.03		
6	0.36			0.03		
INDICATOR LOCATION	Deflection at +120.00 psf	DEFLECTION (in.)		Permanent Set at +120.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	0.47	0.05	0.27	0.04	0.01	N/A
2	0.47			0.04		
3	0.38			0.03		
4	0.47	0.02	0.20	0.05	0.01	
5	0.47			0.04		
6	0.50			0.04		



**TEST REPORT FOR FGM-PARALLEL LLC**

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

**Test Specimen #2C: Preload and Design Load per TAS 202**

INDICATOR LOCATION	Deflection at -90.00 psf	DEFLECTION (in.)		Permanent Set at -90.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	0.88	<0.01	N/A	0.07	<0.01	N/A
2	0.91			0.07		
3	0.94			0.07		
4	0.78	0.10		0.07	<0.01	
5	0.88			0.07		
6	0.79			0.07		
INDICATOR LOCATION	Deflection at -120.00 psf	DEFLECTION (in.)		Permanent Set at -120.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	1.31	0.01	0.27	0.13	<0.01	N/A
2	1.36			0.13		
3	1.40			0.13		
4	1.19	0.12	0.20	0.14	0.01	
5	1.31			0.13		
6	1.19			0.13		

**Test Specimen #1C: Water Penetration per TAS 202**

TITLE OF TEST	RESULTS	ALLOWED	NOTE
Water Penetration, per TAS 202 15% of Positive Design Pressure at 18.00 psf	Pass	No leakage	2

**Note 15:** Without insect screen.

**Test Specimen #1C: Structural Overload Load per TAS 202**

INDICATOR LOCATION	Deflection at +180.00 psf	DEFLECTION (in.)		Permanent Set at +180.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	0.71	0.09	N/A	0.05	0.01	0.06
2	0.74			0.06		
3	0.59			0.05		
4	0.71	0.04		0.06	0.01	0.05
5	0.71			0.05		
6	0.78			0.05		

**TEST REPORT FOR FGM-PARALLEL LLC**

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

**Test Specimen #2C: Structural Overload Load per TAS 202**

INDICATOR LOCATION	Deflection at +180.00 psf	DEFLECTION (in.)		Permanent Set at +180.00 psf	PERMANENT SET (in.)	
		MEASURED	ALLOWED		MEASURED	ALLOWED
1	1.49	0.04	N/A	0.17	0.01	0.06
2	1.46			0.15		
3	1.50			0.15		
4	1.28	0.21		0.16	0.02	0.05
5	1.49			0.17		
6	1.28			0.15		

**Note 16:** Positive and negative uniform static load test loads were held for 30 seconds.

**Note 17:** Tape and film were used to seal against air leakage during structural testing. In our opinion, the tape and film did not influence the results of the test.

**Note 18:** See Sketch #2 for indicator locations. Deflection/permanent set reported is the overall deflection between three points (longest unsupported span) which accounts for support movement.

**Protocol TAS 201-94, Large Missile Impact Procedures**

Test Date: 02/14/25

The temperature during testing was 67°F. The results are tabulated as follows:

**Test Specimen #3C**

IMPACT #	MISSILE WEIGHT (lbs.)	MISSILE LENGTH (in.)	MISSILE VELOCITY (ft./sec.)	OBSERVATIONS
1	9.25	108	50.2	Denting on cladding, sheathing damaged, no missile penetration
2			50.3	Denting on cladding, sheathing damaged, no missile penetration
3			50.2	Denting on cladding, sheathing damaged, no missile penetration

**Note 19:** See Sketch #3 for impact locations.

## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

### Protocol TAS 203-94, Cyclic Wind Pressure Loading

Test Date(s): 02/17/25

The temperature during testing was 64°F. The results are tabulated as follows:

#### Test Specimen #3C: Cyclic Test Spectrum and Average Cycle Time per TAS 203

DESIGN PRESSURE	STAGE		
+120.00 / -120.00 psf	1	2	3
POSITIVE PRESSURE RANGE (psf)	0 – 60.00	0 – 72.00	0 – 156.00
AVERAGE CYCLE TIME (sec.)	2.95	3.20	N/A
NUMBER OF CYCLES	600	70	1
	4	5	6
NEGATIVE PRESSURE RANGE (psf)	0 – 60.00	0 – 72.00	0 – 156.00
AVERAGE CYCLE TIME (sec.)	3.00	2.98	N/A
NUMBER OF CYCLES	600	70	1

#### Test Specimen #3C: Positive Cyclic Load per TAS 203

INDICATOR LOCATION	NET MAXIMUM DEFLECTION (in.)	NET PERMANENT SET (in.)	PERCENT RECOVERY	
			MEASURED %	ALLOWED %
1-3	0.180	0.015	92	> 90
4-6	0.215	<0.010	>99	> 90

#### Test Specimen #3C: Negative Cyclic Load per TAS 203

INDICATOR LOCATION	NET MAXIMUM DEFLECTION (in.)	NET PERMANENT SET (in.)	PERCENT RECOVERY	
			MEASURED %	ALLOWED %
1-3	0.085	<0.010	>99	> 90
4-6	0.215	0.020	91	> 90

**Note 20:** See Sketch #2 for indicator locations. Deflection/permanent set reported is the overall deflection between three points (longest unsupported span) which accounts for support movement.

## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

### SECTION 9

#### CONCLUSIONS

The large missiles impacted each intended target. Each impact location was carefully inspected. No signs of penetration, rupture, or opening after the large missile impact test were observed; as such, each test specimen satisfies the large missile requirements of TAS 201. Upon completion of testing, specimens tested for TAS 201-94 met the requirements of Section 1626 of the Florida Building Code, Building.

No signs of failure were observed in any area of the test specimen during the TAS 202 testing; as such, the test specimen satisfies the requirements of TAS 202. Upon completion of testing, specimens tested for TAS 202-94 met the requirements of Section 1620 of the Florida Building Code, Building.

No signs of failure were observed in any area of the test specimens during the cyclic load test; as such, the test specimens satisfy the cyclic load requirements of TAS 203. Upon completion of testing, specimens tested for TAS 203-94 met the requirements of Section 1625 of the Florida Building Code, Building.

Unless differently required, Intertek reports apply the "Simple Acceptance" rule, also called "Shared Risk approach," of ILAC-G8:09/2019, Guidelines on Decision Rules and Statements of Conformity.

## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

### SECTION 10 SKETCHES

REV	DATE	DESCRIPTION	BY				
<b>SPECIMENS 1A - 5A</b>							
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;">PROJECT NO. R9929.01 109-18</td> <td style="width: 25%;">PROJECT NAME TAS 202/203 CLIENT: FGM-PARALLEL</td> <td style="width: 25%; text-align: center;"> </td> <td style="width: 25%;">DRAWN BY ALW DATE 04/04/2025</td> </tr> </table>				PROJECT NO. R9929.01 109-18	PROJECT NAME TAS 202/203 CLIENT: FGM-PARALLEL		DRAWN BY ALW DATE 04/04/2025
PROJECT NO. R9929.01 109-18	PROJECT NAME TAS 202/203 CLIENT: FGM-PARALLEL		DRAWN BY ALW DATE 04/04/2025				
SPECIMENS 1A • 5A INDICATOR LOCATIONS			SHEET 1 of 1				

Sketch No. 1


Test Specimens 1A through 5A TAS 202/203 Indicator Locations

## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25



Sketch No. 2

Test Specimens 1B through 3C TAS 202/203 Indicator Locations

## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

	REV	DATE	DESCRIPTION	BY																
<b>SPECIMEN 3C</b>																				
<table border="1" style="margin: auto; border-collapse: collapse;"> <tr><td colspan="2" style="height: 20px;"></td></tr> <tr><td style="width: 30%; height: 20px;"></td><td style="width: 70%; height: 20px;"></td></tr> <tr><td colspan="2" style="text-align: center; height: 20px;">③</td></tr> <tr><td style="width: 60%; height: 20px;"></td><td style="width: 40%; height: 20px;"></td></tr> <tr><td colspan="2" style="text-align: right; height: 20px;">②</td></tr> <tr><td style="width: 30%; height: 20px; text-align: center;">①</td><td style="width: 70%; height: 20px;"></td></tr> <tr><td colspan="2" style="height: 20px;"></td></tr> <tr><td colspan="2" style="height: 20px;"></td></tr> </table>									③				②		①					
③																				
②																				
①																				
PROJECT NO. R9929.01 109-18	PROJECT NAME TAS 203 CLIENT FGM-PARALLEL		DRAWN BY SPECIMEN 3C IMPACT LOCATIONS	DWG. BY ALW DATE 04/04/2325	SHEET 1 of 1															

**Sketch No. 3**  
**Test Specimen 3C TAS 203 Impact Locations**

## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

### SECTION 11

#### PHOTOGRAPHS



**Photo No. 1**  
**C-B6, 6" Profile Cladding**



## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25



**Photo No. 2**  
**C-B12, 12" Profile Cladding**



Total Quality. Assured.

130 Derry Court  
York, Pennsylvania 17406

Telephone: 717-764-7700  
Facsimile: 717-764-4129  
[www.intertek.com/building](http://www.intertek.com/building)

## TEST REPORT FOR FGM-PARALLEL LLC

Report No.: R9929.01-109-18 R1


Date: 05/01/25

Revision 1: 05/13/25


### SECTION 12

#### DRAWINGS

The test specimen drawings have been reviewed by Intertek B&C and are representative of the test specimen(s) reported herein. Test specimen construction was verified by Intertek B&C per the drawings included in this report. Any deviations are documented herein or on the drawings.





1 **STUD ELEVATION**



2 **CLADDING ELEVATION**

NOTES:


- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 1-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 24" O.C. INTO WOOD STUDS
- EXPANSION CLIPS 32" O.C. MAX
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 1-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 32" O.C. INTO WOOD STUDS
- AIR AND WATER MEMBRANE
- PARALLEL AP C-B6 CLADDING BOARD
- PARALLEL AP C-STR STARTER EXTRUSION
- 2 X 6 WOOD STUD
- 5/8" TRUE PLYWOOD



**3** TOP OF WALL DETAIL  
3" = 1'-0"

NOTES:


- EXPANSION CLIPS 32" O.C. MAX
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 1-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 32" O.C. INTO WOOD STUDS
- AIR AND WATER MEMBRANE
- PARALLEL AP C-B6 CLADDING BOARD
- 5/8" TRUE PLYWOOD
- 2 X 6 WOOD STUD



**2** TYPICAL HORIZONTAL DETAIL  
3" = 1'-0"

NOTES:


- EXPANSION CLIPS 32" O.C. MAX
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 1-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 32" O.C. INTO WOOD STUDS
- AIR AND WATER MEMBRANE
- PARALLEL AP C-B6 CLADDING BOARD
- PARALLEL AP T-TTF TRIM
- PARALLEL AP T-TTM TRIM
- 5/8" TRUE PLYWOOD
- 2 X 6 WOOD STUD
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 1-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 24" O.C. INTO WOOD SILL




**1** SILL DETAIL  
N.T.S.

NOTES:


- PARALLEL AP T-TTF TRIM
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 1-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 24" O.C. INTO WOOD STUDS
- PARALLEL AP C-B6 CLADDING BOARD
- AIR AND WATER MEMBRANE
- 5/8" TRUE PLYWOOD
- 2 X 6 WOOD STUD
- PARALLEL C-TTM TRIM



**4** JAMB DETAIL  
3" = 1'-0"



1 **STUD ELEVATION**




2 **CLADDING ELEVATION**

NOTES:

- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 2-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 24" O.C. INTO WOOD STUDS
- EXPANSION CLIPS 16" O.C. MAX
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 2-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 32" O.C. INTO WOOD STUDS
- AIR AND WATER MEMBRANE
- PARALLEL AP C-B12 CLADDING BOARD
- PARALLEL AP C-STR STARTER EXTRUSION
- 2 X 6 WOOD STUD
- 5/8" TRUE PLYWOOD


intertek  
 Report #: R9929.01  
 Date: 04/07/25  
 Verified by: [Signature]



3 TOP OF WALL DETAIL  
 3" = 1'-0"

NOTES:


- EXPANSION CLIPS 16" O.C. MAX
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 2-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 32" O.C. INTO WOOD STUDS
- AIR AND WATER MEMBRANE
- PARALLEL AP C-B12 CLADDING BOARD
- 5/8" TRUE PLYWOOD
- 2 X 6 WOOD STUD



2 TYPICAL HORIZONTAL DETAIL  
 3" = 1'-0"

NOTES:


- EXPANSION CLIPS 16" O.C. MAX
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 2-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 16" O.C. INTO WOOD STUDS
- AIR AND WATER MEMBRANE
- PARALLEL AP C-B12 CLADDING BOARD
- PARALLEL AP T-TTF TRIM
- PARALLEL AP T-TTM TRIM
- 5/8" TRUE PLYWOOD
- 2 X 6 WOOD STUD
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 2-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 24" O.C. INTO WOOD SILL



1 SILL DETAIL  
 N.T.S.

NOTES:


- PARALLEL AP T-TTF TRIM
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 2-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 24" O.C. INTO WOOD STUDS
- PARALLEL AP C-B12 CLADDING BOARD
- AIR AND WATER MEMBRANE
- 5/8" TRUE PLYWOOD
- 2 X 6 WOOD STUD
- PARALLEL C-TTM TRIM




4 JAMB DETAIL  
 3" = 1'-0"

NOTES:


- PARALLEL C-EC EXPANSION CLIP
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 2-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 24" O.C. INTO WOOD STUDS
- PARALLEL AP C-B6 CLADDING BOARD
- AIR AND WATER MEMBRANE
- 5/8" TRUE PLYWOOD
- 2 X 6 WOOD STUD



5 JOINER DETAIL  
 3" = 1'-0"





1 STUD ELEVATION



2 CLADDING ELEVATION

NOTES:


- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 2-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 24" O.C. INTO WOOD STUDS
- EXPANSION CLIPS 16" O.C. MAX
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 2-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 16" O.C. INTO WOOD STUDS
- AIR AND WATER MEMBRANE
- PARALLEL AP C-B12 CLADDING BOARD
- PARALLEL AP C-STR STARTER EXTRUSION
- 2 X 6 WOOD STUD
- 5/8" DENSGLOSS



**3** TOP OF WALL DETAIL  
3" = 1'-0"

NOTES:


- EXPANSION CLIPS 16" O.C. MAX
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 2-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 16" O.C. INTO WOOD STUDS
- AIR AND WATER MEMBRANE
- PARALLEL AP C-B12 CLADDING BOARD
- 5/8" DENSGLOSS
- 2 X 6 WOOD STUD



**2** TYPICAL HORIZONTAL DETAIL  
3" = 1'-0"

NOTES:


- EXPANSION CLIPS 16" O.C. MAX
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 2-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 16" O.C. INTO WOOD STUDS
- AIR AND WATER MEMBRANE
- PARALLEL AP C-B12 CLADDING BOARD
- PARALLEL AP T-TTF TRIM
- PARALLEL AP T-TTM TRIM
- 5/8" DENSGLOSS
- 2 X 6 WOOD STUD
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 2-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 24" O.C. INTO WOOD SILL



**1** SILL DETAIL  
N.T.S.

NOTES:


- PARALLEL AP T-TTF TRIM
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 2-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 24" O.C. INTO WOOD STUDS
- PARALLEL AP C-B12 CLADDING BOARD
- AIR AND WATER MEMBRANE
- 5/8" DENSGLOSS
- 2 X 6 WOOD STUD
- PARALLEL C-TTM TRIM



**4** JAMB DETAIL  
3" = 1'-0"

NOTES:

- PARALLEL C-EC EXPANSION CLIP
- #10 - PANEL-TITE BURR BUSTER METAL TO WOOD X 2-1/2" CARBON STEEL (MIAMI DADE COUNTY APPROVED) SCREWS 24" O.C. INTO WOOD STUDS
- PARALLEL AP C-B12 CLADDING BOARD
- AIR AND WATER MEMBRANE
- 5/8" DENSGLOSS
- 2 X 6 WOOD STUD



**5** JOINER DETAIL  
3" = 1'-0"



# C-B6 | 6" Cladding/Soffit Board

Part Drawing 2025



- NOTES:
- ALUMINUM ASSOCIATION STANDARD TOLERANCES APPLY UNLESS OTHERWISE SPECIFIED
  - 6063-T5
  - POWDER COATED
  - AAMA 2604
  - SOLID POWDER AVG. COATING THICKNESS SHALL BE 2.0-2.5 MILS
  - STF POWDER AVG. COATING THICKNESS SHALL BE 3.5-4.0 MILS
  - DIMENSIONS SHOWN APPLY BEFORE POWDER COATING

C-B6  
DIE NUMBER  
DRAWING NUMBER  
ID =XXXX


**PARALLEL**  
ARCHITECTURAL PRODUCTS

Parallel Architectural Products	
CUSTOMER NAME	A
PART NAME	6" CLADDING/SOFFIT
PART NO	X
DATE	02-10-2025

C-B6	
DIE NUMBER	
DRAWING NUMBER	
LB/FT	0.6563
AREA	0.5581
PERI	19.8487
ADJ PERI	----
CCIFAC	X   X
TYPE	SOLID
TIE.VOL	----
DRN BY	KGM
DIE SIZE	---
FD PLT	----
BACKER	XXXX
BOLSTER	X
SUB BOL	X
HOLE	X
BILIR/R	X   X

**intertek**  
Total Quality Assured.

Report #: R9929.01  
Date: 05/13/25  
Verified by: *RRZ*



REV A  
XXX

NOTES:

- 1. ALUMINUM ASSOCIATION STANDARD TOLERANCES APPLY UNLESS OTHERWISE SPECIFIED
- 2. 6063-T5
- 3. POWDER COATED
- 4. AAMA 2604
- 5. SOLID POWDER AVG. COATING THICKNESS SHALL BE 2.0-2.5 MILS
- 6. STF POWDER AVG. COATING THICKNESS SHALL BE 3.5-4.0 MILS
- 7. DIMENSIONS SHOWN APPLY BEFORE POWDER COATING

C-B12	DIE NUMBER	DRAWING NUMBER	FGM - PARALLEL LLC	
			CUSTOMER NAME A	
			PART NAME 12" CLADDING/SOFFIT	
			PART NO X	DATE 04/01/2025

C-B12	
DIE NUMBER	
-----	
DRAWING NUMBER	


LB/FT	1.5765
AREA	1.3406
PERI	33.1932
ADJ PERI	-----
CCIFAC	X   X
TYPE	SOLID
TIE.VOL	-----
DRN BY	KGM
DIE SIZE	---
FD PLT	-----
BACKER	XXXX
BOLSTER	X
SUB BOL	X
HILES	X
BILIR/R	X   X



INTERLOCKING PART



Report #: R9929.01  
 Date: 05/13/25  
 Verified by: *J.R.Z.*



EXPOSED SURFACE

02/10/2025  
REV A

# C-EC | Cladding Clip

## Part Drawing 2025




- NOTES:  
 1. ALUMINUM ASSOCIATION STANDARD TOLERANCES  
 APPLY UNLESS OTHERWISE SPECIFIED  
 2. 6063-T5

DIE NUMBER	DRAWING NUMBER	<b>PARALLEL</b> ARCHITECTURAL PRODUCTS		<b>Parallel Architectural Products</b>		C-EC	
		ID =XXXX		CUSTOMER NAME		A	
		PART NAME XXXX		PART NO X		DATE 11-1-2023	



Report #: R9929.01  
 Date: 05/13/25  
 Verified by: *JRW*

DRAWING NUMBER	----
LB/F/T	0.000
AREA	0.1077
PERI	3.4887
ADJ PERI	----
CCIFAC	X   X
TYPE	SOLID
TIE.VDL	----
DRN BY	KGM
DIE SIZE	---
FD PLT	----
BACKER	XXXX
BOLSTER	X
SUB BOL	X
HOLE	X
BILIR/R	X   X



REV A

# C-STR | Starter Strip

## Part Drawing 2025



**NOTES:**

- ALUMINUM ASSOCIATION STANDARD TOLERANCES APPLY UNLESS OTHERWISE SPECIFIED
- 6063-T5
- POWDER COATED
- AAMA 2604
- SOLID POWDER AVG. COATING THICKNESS SHALL BE 2.0-2.5 MILS
- STF POWDER AVG. COATING THICKNESS SHALL BE 3.5-4.0 MILS
- DIMENSIONS SHOWN APPLY BEFORE POWDER COATING

C-STR

DIE NUMBER

DRAWING NUMBER

ID =XXXX



**PARALLEL**  
ARCHITECTURAL PRODUCTS

Parallel Architectural Products

CUSTOMER NAME		A
PART NAME	XXXX	
PART NO	X	DATE 03/25/2025

C-STR

DIE NUMBER

-----

DRAWING NUMBER

LB/FT 0.243

AREA 0.2075

PERI 7.5475

ADJ PERI -----

CCIFAC X X

TYPE SOLID

TIE.VOL -----

DRN BY KGM

DIE SIZE ---

FD PLT -----

BACKER XXXX

BOLSTER X


SUB BOL X

HOLES X

BILIR/R X X

<p>Total Quality. Assured.</p>	Report #:	R9929.01
	Date:	05/13/25
	Verified by:	<i>JRW</i>

EXPOSED SURFACE



REV A XXX

# C-TTF | Flashing Top Clip

## Part Drawing 2025



- NOTES:
- ALUMINUM ASSOCIATION STANDARD TOLERANCES APPLY UNLESS OTHERWISE SPECIFIED
  - 6063-T5
  - POWDER COATED
  - AAMA 2604
  - SOLID POWDER AVG. COATING THICKNESS SHALL BE 2.0-2.5 MILS
  - STF POWDER AVG. COATING THICKNESS SHALL BE 3.5-4.0 MILS
  - DIMENSIONS SHOWN APPLY BEFORE POWDER COATING

C-TTF  
DIE NUMBER  
DRAWING NUMBER  
ID =XXXX



Parallel Architectural Products

CUSTOMER NAME A  
PART NAME FLASHING TOP CLIP  
PART NO X DATE 03/26/2025

C-TTF

DIE NUMBER

-----

DRAWING NUMBER

LB/FT 0.244

AREA 0.2088

PERI 6.6876

ADJ PERI -----

CCIFAC X X

TYPE SOLID

TIE.VOL -----

DRN BY KGM

DIE SIZE ---

FD PLT -----

BACKER XXXX

BOLSTER X


SUB BOL X

HOLES X

BILIR/R X X

**intertek**  
Total Quality. Assured.

Report #: R9929.01  
Date: 05/13/25  
Verified by: *JRW*



REV A  
xxx

# C-TTM | Flashing Base Clip

Part Drawing 2025



**NOTES:**

- |  |  |
|--|--|
| 1. ALUMINUM ASSOCIATION STANDARD TOLERANCES APPLY UNLESS OTHERWISE SPECIFIED | 4. AAMA 2604   |
| 2. 6063-T5   | 5. SOLID POWDER AVG. COATING THICKNESS SHALL BE 2.0-2.5 MILS |
| 3. POWDER COATED   | 6. STF POWDER AVG. COATING THICKNESS SHALL BE 3.5-4.0 MILS   |
|  | 7. DIMENSIONS SHOWN APPLY BEFORE POWDER COATING              |

C-TTM

DIE NUMBER

DRAWING NUMBER

ID =XXXX



**PARALLEL**  
ARCHITECTURAL PRODUCTS

Parallel Architectural Products

CUSTOMER NAME		A
PART NAME	FLASHING BASE CLIP	
PART NO	X	DATE 03/26/2025

C-TTM

DIE NUMBER

-----

DRAWING NUMBER

LB/FT 0.202

AREA .1724

PERI 6.4255

ADJ PERI -----

CCIFAC X | X

TYPE SOLID

TIE.VOL -----

DRN BY KGM

DIE SIZE ---

FD PLT -----

BACKER XXXX

BOLSTER X

SUB BOL X

HILES X

BILIR/R X | X




Total Quality. Assured.

Report #: R9929.01

Date: 05/13/25

Verified by: *J.R.T.*



REV A XXX



Total Quality. Assured.

130 Derry Court  
York, Pennsylvania 17406

Telephone: 717-764-7700  
Facsimile: 717-764-4129  
[www.intertek.com/building](http://www.intertek.com/building)

**TEST REPORT FOR FGM-PARALLEL LLC**

Report No.: R9929.01-109-18 R1

Date: 05/01/25

Revision 1: 05/13/25

**SECTION 13**

**REVISION LOG**

REVISION #	DATE	PAGES	REVISION
0	05/01/25	N/A	Original Report Issue
1	05/13/25	29-40	Revised drawing packet.